


REDLINE / WEBER CARBURETORS

32 / 36 DFEV - DFAV

PROGRESSIVE SERIES
22680 056 DFAV
22680 070 DFEV



Common Parts

Rebuild Kit

92-3230-05

Base gasket Kit

99005-068

Carburetor Rebuild kit does not include

Power Valve Assembly

54a) Electric Choke

57804-332

10) Power Valve Diap.


57804-096

73) Accelerator Pump Diap

47407-016

15) Idle Jet Holder

52570-005



Float setting notes

1. Fuel pressure is critical to float spillage. Redline recommends 2.5 to 3 lbs.
2. For aggressive off-road use float drop should be limited to 43mm max drop setting. This is done by setting tab A to limit drop.

KEY CALIBRATED PARTS

- 11) 79516-xxx Needle & Seat
- 13) 41030-022 Float
- 80) 73801-xxx Main Jet
- 5) 77201-xxx Air corrector Jet
- 15) 74403-xxx Idle Jet
- 9) 76211-xxx Accelerator pump Jet
- 76215-xxx Performance Double pump jet